BANGALORE WATER SUPPLY AND SEWERAGE BOARD

WORK NAME : -

For the work Providing & Laying of 300mm dia and 230mm dia SW sewer pipeline at Shanthi Veterana Lane coming under Chickkalal bagh S/stn of AEE SW-1 Sub Division.

SCALE:-HOR: 1:1000/VER: 1:100

JE | AEE SW-1

LEGEND

- Proposed Alignment
- Proposed / Reconstruction MH's
- GL
- IL
- Road
- SWD
- Flow Direction

DIA OF PIPE	STATION	CUMULATIVE CHAINAGE (m)	DISTANCE (m)	MACHINHOLE DEPTH (m)	INVERT LEVEL (m)	GROUND LEVEL (m)
300mm dia SW PIPE	ExMH-1	0.00	0.00	1.20	928.740	929.940
	2	16.00	16.00	1.30	929.285	930.585
	3	16.00	16.00	1.50	929.730	931.230
	4	17.00	17.00	1.50	930.520	932.020
	5	21.00	21.00	1.30	931.040	932.340
	6	26.00	4.00	1.00	931.580	932.580
	7		4.00	1.00	931.555	932.655
230mm dia SW PIPE	8	17.00	5.00	1.20	932.30	933.50
	9		5.00	1.20	932.380	933.580
	10	25.00	25.00	1.00	933.090	934.090
	11	147.00	0.00	1.00	929.180	930.180
	12	178.50	31.50	1.20	929.450	930.650
	13	203.50	25.00	1.50	929.730	931.230

Datum: 925.0

Scanned with OKEN Scanner

For the work Providing & Laying of 300mm dia and 230mm dia SW sewer pipeline at Shanthi Veeranna Lane coming under Chickkalal bagh S/stn of AEE SW-1 Sub Division.

JE CLB S/Stn

AEE SW-1

Scanned with OKEN Scanner

Google Maps

For the work Providing & Laying of 300mm dia and 230mm dia SW sewer pipeline at Shanthi Veeranna Lane coming under Chickkalal bagh S/stn of AEE SW-1 Sub Division.

Measure distance

Total distance: 259.07 m (849.98 ft)

JE - CM

Scanned with OKEN Scanner